Abstract estimate for restoring Sahasravalli Voddu R. No. 1744 of Shikarpur Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Clearing jungle, cutting and removing trees, with roots, etc.	L. S.	..	..	50
2	Earthwork approach and draft clearing and widening the earth to fill up the breach and to form bank with a lead of 200'	C.yd.	0 5 0	4,200	
3	Earthwork excavating foundation and using the soil to form spoil bank with a lead of 200'	..	0 5 0	658	
4	Stone jelly concrete in cement mortar 1 : 5 : 10	C.ft.	0 8 0	1,283	
5	Size stone in cement mortar 1 : 6	,,	0 8 0	3,732	
6	Cement pointing	Sqr.	4 8 0	22.28	
7	Cement concrete coping 1 : 2 : 4	C.ft.	1 0 0	210	
8	Cement plastering 1 : 3, ½" thick	Sqr.	9 0 0	2.40	
9	Rough stone work new	C.yd.	2 8 0	326	
10	Jelly filling below apron	,,	1 0 0	90	
11	Cement concrete grouting to surface of apron	Sqr.	5 0 0	56.32	
12	Providing and fixing M. S. M. rails 40 lbs. per Sq. foot up right as shown in plan 3' c to c including cost and carting, etc., complete	R.ft.	0 12 0	240	
13	Removing loose stone, and silt at the site of breach and cutting grips and steps	L.S.	..	..	100
14	Earthwork for breach filling mixed with ⅛ gravel including watering, tamping and consolidation, etc. (only consolidation charges)	C.yd.	0 2 0	508	
15	Collecting and mixing gravel for breach with lead.	,,	0 12 0	72	
16	Bailing water	L. S.	..	..	50
17	Forming approach road of 5 miles to work spot, levelling the slope of earthen bank down stream, etc.	L.S.	..	..	
18	Construction of relieving weirs in the existing channel	...	..	240	

D. A. HUKERI,
Executive Engineer.

KADUR DIVISION.

Abstract Notification.

The attention of the public is invited to the notification published on pages 834-836 of the *Mysore Gazette*, Part VI, dated 4th May 1939, calling for tenders for "Constructing a Girder Bridge across Megarmakki Halla on Narasimharajapura-Balehonnur Road" in Kadur District.

The last date for the receipt of Tenders is 22nd May 1939.

Estimate .. Rs. 16,380. Deposit Amount .. Rs. 820.

Abstract Notification.

The attention of the public is invited to the Notification published in pages 836-838, Part VI of the *Mysore Gazette*, dated 4th May 1939, calling for tenders for the work of constructing a Girder Bridge across Dhobi Halla on Balehonnur-Narasimharajapura Road.

The last date for receipt of tender in this office is 22nd May 1939.

Estimate .. Rs. 11,800. Deposit .. Rs. 590.

C. R. IYENGAR,
Executive Engineer.

CHITALDRUG DIVISION.

Abstract Notification dated 29th April 1939.

The attention of the public is invited to the detailed notification dated 29th April 1939, calling for tenders "to construct a new tank at Metikurki, Hiriyur Taluk," published in Part VI, pages 839-841, of the *Mysore Gazette*, dated 4th May 1939.

The latest date for receiving tenders is 2 P.M. on the 22nd May 1939.

Abstract Notification dated 29th April 1939.

The attention of the public is invited to the detailed notification dated 29th April 1939, calling for tenders for "constructing a bridge combined with a causeway across left waste weir valley of Dharmapur tank" published in Part VI, pages 842-843 of the *Mysore Gazette*, dated 4th May 1939.

The latest date for receiving tenders is 13th May 1939 at 2 P.M.

S. RAMASWAMY,
Executive Engineer.

Abstract Notification dated 1st May 1939.

The attention of the public is invited to the notification calling for tenders for "constructing a causeway with undervents across the Vedavati River on Hiriyur-Dharmapur Road" published on pages 844-845, Part VI of the *Mysore Gazette*, dated 4th May 1939. The last date for receipt of tenders is 13th May 1939.

S. NARASAPPA,
For *Executive Engineer.*

Notification dated 6th May 1939.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 2 P.M. on 20th May 1939, for constructing X-Ray room attached to Local Fund Dispensary, Davangere.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for constructing X-Ray room attached to Local Fund Dispensary, Davangere." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a deposit of Rs. 150 (rupees one hundred and fifty only) in cash or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money. The earnest money of the successful tenderer will be retained as security deposit for due fulfilment of the contract. Such a deposit in cash will not carry any interest. The balance of earnest money, *viz.*, Rs. 150 should be given after the tender is accepted.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 20th May 1939 at 4 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental schedule contract form, for the due fulfilment of the contract and for the execution of all items of work in accordance with the Bombay specifications, 1931.

6. Failure to comply with the condition 5 above, or to agree to carry out the work in accordance with the specifications and agreements in force will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of tender notification, contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Re. 1.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof, or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer, on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The work should be completed and handed over in a tidy condition to the Public Works Department by the end of June 1939, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 10 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of dispute of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations, wherever and whenever necessary with his own pumping apparatus, including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P.W.D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by Insurance at the proper time.

(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. Lumpsum items will be paid on detail measurements.
24. Chamundi brand cement alone to be used.

Abstract estimate for constructing X-Ray Ward attached to the Local Fund Dispensary at Davangere.

Item No.	Details of work	Unit	Rate	Quantity	Rates quoted	
					In words	In figures
			Rs. a. p.			Rs.
1	Earthwork excavation and filling in basement	C.yd.	0 3 0	50		
2	Filling in foundation with stone jelly concrete in lime mortar	C.ft.	0 3 6	297		
3	Size stone in mortar foundation with bond stones 6′ apart	,,	0 4 6	1,238		
4	Burnt brick in mortar for superstructure ..	,,	0 4 0	1,412		
5	Cement concrete slabs 1 : 3 : 6	,,	0 8 0	34		
6	Burnt stone slabs 6″ thick roughly dressed and fixed in mortar	S.ft.	0 8 0	216		
7	Roofing with R.C.C. wedge shaped joists and brick nogged terrace and two courses of flat tiles and plastered on both sides with white washing, etc., complete in every respect	Sqr.	55 0 0	7.45		

Item No.	Details of work	Unit	Rate	Quantity	Rates quoted	
					In words	In figures
			Rs. a. p.		Rs.	
8	Band cornice of brick in mortar 6″ deep and 1½″ projection with plastering complete as per approved design	R.ft.	0 3 0	148		
9	Supplying and fixing rolled steel girders of tested quality with two coats of corrosive paints, etc., complete	Cwt.	15 0 0	12½		
10	Boxing the girders	R.ft.	0 6 0	60		
11	Plain parapet wall of brick in mortar 9″ thick and 9″ high with plastering and white washing, etc., as per approved design	,,	0 4 0	159		
12	Teakwood doors 4′×7′ with panelled shutters, bolts, nuts ,hinges and locking arrangements, etc., complete with two coats of best approved paint complete ..	S.ft.	1 10 0	112		
13	Teakwood windows 3′×4½′ with glazed shutters and welded mesh with all fittings, etc., complete with two coats of best approved paint	,,	1 8 0	99		
14	Supplying and fixing R.C.C. perforated ventilators	,,	1 0 0	60		
15	2′ wide R.C.C. fret board between pillars including fixing and of approved design.	,,	1 0 0	71		
16	Smooth lime mortar plastering	Sqr.	3 0 0	29.38		
17	Flooring wito 3″ lime mortar concrete and 1½″ (1 : 2 : 4) cement concrete and ½″ topping of cement plastering rubbed smooth and finished red	,,	20 0 0	6.16		
18	White washing, two coats as per plastering.	,,	0 4 0	29.38		
19	Zinc down water pour pipes of 4″ diameter.	R.ft.	..	..		
20	Cement pointing to basement	Sqr.	4 0 0	1.71		
21	Unforeseen and sundries as per actual execution					

K. SUBBA RAO,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS

OFFICE OF THE INSPECTOR-GENERAL OF POLICE IN MYSORE, BANGALORE.

Notice No. T. C. 295—37-38, *dated* 19*th November* 1937.

The public are hereby informed that an Avery's Weigh-bridge to weigh motor vehicles is erected in the Office of the Inspector-General of Police in Mysore, Cenotaph Road, Bangalore City, and that motor vehicles brought for weighment will be weighed on payment of a fee of Rs. 10 for each weighment. A certificate of weighment will invariably be issued with each weighment so made.

F. A. HAMILTON,
Inspector-General of Police.

Notification.

In modification of the notification published on page 787 of Part VI of the *Mysore Gazette*, dated 27th April 1939, regarding the sale of one automatic pistol, six revolvers and two rifles by the District Superintendent of Police, Provincial Reserve Police, on 15th May 1939, the public are hereby informed that the sale of these weapons has been withheld for the present.

E. G. B. PEEL,
Inspector-General of Police.